

This is to inform you that this hospital is in need of replacement of R.O. membrane (qty-02) installed in the water treatment unit of Hemodialysis unit along with AMC for RO plant with a capacity of 500

L/hr in the dialysis dept of this hospital.

You are requested to inspect the unit, if required and to submit the rate quotation/proposal in a sealed envelope in the following format up to 31 st January 2025.

Item name-

Make-

Rate per unit (Rs.)

GST-

Warranty-

AMC Charges per year

Note-

- 1) The firm will install the RO membrane in the existing RO plant in hemodialysis unit.
- 2)The firm will ensure satisfactory product water report with reference to chemical and microbiological purity as per AAMI standard after successful installation of RO membrane.
- 3) TDS of the product water should be less than 20 mg/L.
- 4) Conductivity of product water should be less than 20 $\mu$ S/cm.

Maintenance Branch,  
Room No. 4 ,  
Administrative Block,  
CNBC, Geeta Colony  
9868065559